TABLE OF LANDSCAPING REQUIREMENTS		
WHOLE SITE LANDSCAPING REQUIREMENT PER WESTFIELD ZONING		
REQUIRED PER DWELLING UNIT		TOTAL REQUIRED
SHADE TREE:	4	160
FLOWERING OR EVERGREEN TREE:	2	80
SHRUBS:	4	160
LOT LANDSCAPING PER PUD (COUNTS TOWARD WHOLE SITE TOTAL)		
REQUIRED LANDSCAPING PER LOT		TOTAL REQUIRED
SHADE TREE PER LOT:	2	80
FLOWERING TREE PER LOT:	1	40
CONIFER TREE PER LOT:	1	40
3-4" TALL SHRUB PER LOT:	8	360
18-24" TALL SHRUB PER LOT:	12	480
ROAD FRONTAGE LANDSCAPING REQUIREMENT PER WESTFIELD ZONING 1 SHADE TREE/30 LINEAR FEET (COUNTS TOWARD WHOLE SITE TOTAL)		
TOTAL REQUIRED ALONG CAREY RD:	28	
TOTAL REQUIRED ALONG 169TH ST:	28	
TOTAL:	56	
ROAD FRONTAGE LANDSCAPING REQUIREMENT PER WESTFIELD ZONING 1 EVERGREEN TREE & 5 EVERGREEN SHRUBS/30 LINEAR FEET (DOES NOT COUNT TOWARD WHOLE SITE TOTAL)		
TOTAL TREES ALONG SOUTH BORDER:	38	
TOTAL SHRUBS ALONG SOUTH BORDER:	190	

TOTAL REQUIRED PLANTS	
SHADE TREE:	160
FLOWERING TREE:	40
EVERGREEN TREE:	78
TOTAL TREES:	278
EVERGREEN SHRUBS:	190
3-4" TALL SHRUBS:	360
18-24" TALL SHRUBS:	480
TOTAL SHRUBS:	1030

TOTAL PROVIDED PLANTS	
SHADE TREE:	210
FLOWERING TREE:	40
EVERGREEN TREE:	138
TOTAL TREES:	388
EVERGREEN SHRUBS:	231
3-4" TALL SHRUBS:	380
18-24" TALL SHRUBS:	480
TOTAL SHRUBS:	1091

WALNUT RIDGE ESTATES

Date: 01-29-2013

WEIHE ENGINEERS
10505 N. College Avenue
Indianapolis, Indiana 46280
weihe.net
317 | 846 - 6611

NTS

LOCATION: H:\2012\W10359\Engineering\design\exhibits\Preliminary Landscape exhibit.dwg
DATE/TIME: January 30, 2013 - 3:19pm
PLOTTED BY: pattersing