TABLE OF LANDSCAPING REQUIREMENTS

WHOLE SITE LANDSCAPING REQUIREMENT PER WESTFIELD ZONING		
REQUIRED PER DWELLING UNIT		TOTAL REQUIRED
SHADE TREE:	4	160
FLOWERING OR EVERGREEN TREE:	2	80
SHRUBS:	4	160
LOT LANDSCAPING PER COMMITMENTS (COUNTS TOWARD WHOLE SITE TOTAL)		
REQUIRED LANDSCAPING PER LOT		TOTAL REQUIRED
SHADE TREE PER LOT:	2	80
FLOWERING TREE PER LOT:	1	40
CONIFER TREE PER LOT:	1	40
3-4' TALL SHRUB PER LOT:	8	360
18-24" TALL SHRUB PER LOT:	12	480
ROAD FRONTAGE LANDSCAPING REQUIREMENT PER WESTFIELD ZONING 1 SHADE TREE/30 LINEAR FEET (COUNTS TOWARD WHOLE SITE TOTAL)		
TOTAL REQUIRED ALONG CAREY RD:	28	
TOTAL REQUIRED ALONG 169TH ST:	28	
TOTAL:	56	
BUFFER YARD LANDSCAPING REQUIREMENT PER WESTFIELD ZONING 1 EVERGREEN TREE & 5 EVERGREEN SHRUBS/30 LINEAR FEET (DOES NOT COUNT TOWARD WHOLE SITE TOTAL)		
TOTAL TREES ALONG SOUTH BORDER:	38	
TOTAL SHRUBS ALONG SOUTH BORDER:	190	

TOTAL REQUIRED PLANTS

SHADE TREE:	160
FLOWERING TREE:	40
EVERGREEN TREE:	78
TOTAL TREES:	278
EVERGREEN SHRUBS:	190
3-4' TALL SHRUBS:	360
18-24" TALL SHRUBS:	480
TOTAL SHRUBS:	1030

TOTAL PROVIDED PLANTS

SHADE TREE:	217
FLOWERING TREE:	40
EVERGREEN TREE:	165
TOTAL TREES:	422
EVERGREEN SHRUBS:	223
3-4' TALL SHRUBS:	380
18-24" TALL SHRUBS:	480
TOTAL SHRUBS:	1083

* COUNT OF PROVIDED PLANTS INCLUDES LOT PLANTINGS NOT SHOWN IN PLAN.

LEGEND	SIZE AT INSTALLATION
= EXISTING SHADE TREE	-
= PROPOSED SHADE TREES	8' HIGH & 2" CALIPER
= EXISTING EVERGREEN TREE	-
= PROPOSED EVERGREEN TREE	6' HIGH
= PROPOSED SHRUBS	18" HIGH
= PROPOSED EVERGREEN BUFFER	7' HIGH

WALNUT RIDGE ESTATES

Date: 03-13-2013

WEIHE ENGINEERS
10505 N. College Avenue
Indianapolis, Indiana 46280
weihe.net
317 | 846 - 6611

NTS

LOCATION: H:\2012\W120359\Engineering\design\exhibits\Preliminary Landscape exhibit.dwg
DATE/TIME: March 14, 2013 – 7:44am
PLOTTED BY: petersong