

### **Farr Hills/Buena Vista Sanitary Sewer and Water Extension Project**

The Scope of Work includes the construction of approximately 2786 LFT of subsurface 8" gravity sanitary sewer, approximately 1,340 LFT subsurface 6" force main sanitary sewer of which approximately 578 LFT installed by horizontal directional drilling, approximately 685 LFT of subsurface 10" gravity sanitary sewer installed by jack and bore, a wastewater submersible duplex lift station, and miscellaneous manholes and sanitary service laterals. Also included is approximately 1,393 LFT of subsurface 6" water main, approximately 1,465 LFT of subsurface 8" water main, 8 fire hydrants, and miscellaneous water main fittings, valves, and service laterals. In addition to the construction of sanitary sewers and water mains, the Scope of Work also includes, but is not limited to the following items: milling and resurfacing the entire project's roadways, clearing and grubbing, swale grading, seeding, replacing concrete curb and gutter, and driveway replacement. Maintenance of traffic and installation of temporary control measures are included in the Scope of Work as well.

Engineers Estimate (Construction Cost Only)

Water - \$519,110.00

Sanitary - \$1,378,965.00