



Commercial Inspections

Read all Material

2023 Required Inspections and Procedures

The following inspections are required. The permit card document must be placed in a window visible from the street. Each inspection must be approved prior to proceeding to the next phase of construction. An approved inspection will be indicated by the inspector’s dated signature on the permit card document. If there is no permit card document on site at the time of inspection, the inspection will be considered failed and a fee will be assessed.

Please note that Westfield does not schedule same-day inspections.

Occupying a commercial structure/dwelling before a passed final inspection will result in a \$5000 fine.

Required Inspections

1. Erosion & Infrastructure Prior-**PW**
2. Footing
3. Foundation/Underslab
4. Rough-in
5. Insulation

PW-Public Works

6. Dry-Wall
7. Sump-**PW**
8. Final Building
9. Fire Marshal Inspection
10. Erosion & Infrastructure Final-**PW**

Optional Inspections

1. Pre-Final

Prior Erosion and Sediment/ Infrastructure:

1. Silt fence needs to be around perimeter.
2. Construction drive installed or being installed day of inspection.
3. Inlet protection installed in front and/or rear swales.
4. Concrete washout if applicable.
5. Prior infrastructure will be documented as warranted.

Footing:

1. Grade stakes to be in place for inspection.
2. Check all setbacks to property lines to insure compliance to zoning.
3. Site plan must match the footing that is being poured or all work will discontinue until corrected site plans are submitted, reviewed, and approved.
4. Inspection is required before footing is poured. Do not pour until the inspector has been to inspect. (Pouring a footing before the inspection could result in the removal of all footings and a fine assessed).
5. If partial inspections are to be done, each section must be called in on a daily basis. Do not assume or expect the inspector to show up if an inspection has not been called in.
6. Insulation must be in place.
7. All re-enforcement steel must be in place at this time.

Under slab:

1. Inspection is required after block is laid or walls are poured.
2. Check for anchor bolt on perimeter and center pads.
3. Any/all slab plumbing and/or electrical conduit must be in place at this time.

Rough In: (Building must be weather-tight at this time)

1. The permit card document must be posted for this inspection and those inspections that will follow.
2. All Rough electrical, plumbing, and mechanical must be installed at this time.
3. All doors and windows must be in at this time.
4. DO NOT INSULATE before this inspection. If insulation is installed before this, it will have to be removed then called in for re-inspect.

Insulation:

1. All wall insulation must be in place.

Drywall:

1. Drywall must be installed at this time but not taped or mudded.
2. The inspector will be checking fastener patterns.
3. Nail and screw patterns should be in accordance with Table R702.3.5 of the IRC.

Sump Inspection:

1. Sump line connection will need to be exposed. Inspector will need to see the connection at the stub per Construction Standard Details.
2. Should alternative connection need to be made, please contact Public Works representative for authorization.



Final:

1. All electrical, mechanical, and plumbing work must be complete and operational.
2. All flooring/finishes, walls, and ceilings must be installed.
3. All electrical switch/plug covers must be in place.
4. Electrical panel must be labeled.
5. All landscape/site requirements must be in place at this time and satisfied by the Community Development Department for this inspection in order to receive the C/O.
6. There should be no furniture in the building until a passed final inspection.
7. Any/all re-inspection fees must be paid to receive the Certificate of Occupancy.
8. Finals need to be inspected by the Westfield Fire Marshal.

Final Erosion and Sediment/ Infrastructure:

1. Lot is stabilized with minimum of 70% vegetative cover, mulch or straw blanket.
2. Site grading/drainage features and erosion control completed and required landscaping in place. (Inclement weather-must call in once final stabilization is complete. Refer to point 1).
3. Any inlet protection is removed if applicable.
4. Infrastructure will be documented as warranted. (Sidewalks, driveways, ramps, curbs, storm structures, and swales.)

Final Inspection should be scheduled 3 to 5 days prior to the Builder/Client closing.

Occupying a commercial structure/dwelling before a Certificate of Occupancy will result in a \$5000 fine.



Building Department - 317.804.3170 • Public Works Department - 317.804.3171

Inspection Requests: <https://weconnect.westfield.in.gov/> Phone hours: 8:00 AM-4:00 PM
(Please note, no same day inspections)

Building Division

T.J Wertenberger, Building Commissioner
twertenberger@westfield.in.gov 317.538.3012

Brent Cline, Senior Building Inspector
bccline@westfield.in.gov 317.617.6425

Zach Davis, Senior Building Inspector
zdavis@westfield.in.gov 317.408.6654

Chase Cline, Building Inspector
cccline@westfield.in.gov 317.447.5428

Brett Miller, Building Inspector
bmiller@westfield.in.gov 317.832.5297

Kevin Todd, Community Development Director
ktodd@westfield.in.gov 317.804.3170

Public Works Department:

Adam Essex, Inspection Supervisor
aessex@westfield.in.gov 317.605.3750

Wes Rood, Storm Water Coordinator
wrood@westfield.in.gov 317.504.2477

Brian Paddack, Erosion/Infrastructure
bpaddack@westfield.in.gov 317.409.3626

Driveways & Sidewalks
Westfield Public Works 317.804.3171

John Nail, Public Works Director
jnail@westfield.in.gov 317.804.3171

To: ALL CONTRACTORS AND BUILDERS
Re: BURNING ON CONSTRUCTION SITE

ARTICLE 87: 1997 UNIFORM FIRE CODE STATE OF INDIANA 8704.5 (COMBUSTIBLE DEBRIS) COMBUSTIBLE DEBRIS SHALL NOT BE ACCUMULATED WITHIN THE BUILDING. COMBUSTIBLE DEBRIS, RUBBISH AND WASTE MATERIAL SHALL BE REMOVED FROM BUILDING AS OFTEN AS PRACTICAL. COMBUSTIBLE DEBRIS, WASTE MATERIAL, AND TRASH SHALL NOT BE BURNED ON SITE UNLESS APPROVED BY A VARIANCE.

VIOLATORS ARE SUBJECT TO LEGAL ACTION INCLUDING FINES

VARIANCES ARE CONSIDERED ON A CASE BY CASE BASIS AND APPROVAL MUST BE ATTAINED IN WRITING PRIOR TO BURNING OF ANY WASTE MATERIAL. FOR FURTHER INFORMATION REGARDING VARIANCES CONTACT:

Mr. Brian Callahan
Dept. of Environmental Management
Office of Air Quality
100 N Senate Ave Room IGCN 1003
Indianapolis, IN 46206-6015
317.232.8244

Fire Marshal: Ryan Flora
Division Chief of
Fire Prevention
17535 Dartown Road
Westfield, IN 46074
317.804.3309