

GENERAL LANDSCAPE AND PLANTING NOTES

1. Refer to Project Manual for Planting Specifications and Topsoil requirements. Refer to Plant Schedule and Planting Details for additional information.
2. All materials are subject to the approval of the Landscape Architect and Owner at any time. Landscape Architect to inspect all plant locations and plant bed conditions prior to installation. On-site adjustments may be required.
3. Rootballs shall meet or exceed size standards as set forth in 'American Standards for Nursery Stock'. MAIN LEADERS OF ALL TREES SHALL REMAIN INTACT.
4. Remove from the site any plant material that turns brown or defoliates within five (5) days after planting. Replace immediately with approved, specified material.
5. Plant counts indicated on drawings are for Landscape Architect's use only. Contractor shall make own plant quantity takeoffs using drawings, specifications, and plant schedule requirements (i.e., spacing), unless otherwise directed by Landscape Architect. Contractor to verify bed measurements and install appropriate quantities as governed by plant spacing per schedule. Plant material quantities shown on plan are minimum quantities. Additional material may be needed to meet spacing requirements and field conditions.
6. Seed all areas disturbed by construction activities that are not otherwise noted to receive pavement, planting bed, or sod treatment.
7. The Contractor shall install and/or amend topsoil in all proposed bed areas to meet Specifications. Contractor shall coordinate quantity and placement of topsoil. Landscaper shall verify depth of topsoil prior to plant installation. (Refer to specifications for topsoil source and placement requirements)
8. All tree locations shall be marked with 2x2" stakes prior to planting for review and approval by the Landscape Architect. Any plant material installed in an incorrect location, by the judgment of the Landscape Architect, shall be reinstalled at the Contractor's expense.
9. All plant beds shall receive 3" minimum of shredded hardwood bark mulch (unless otherwise noted).
10. Verify all utility locations in the field prior to beginning work. Repair all damaged utilities to Owner's satisfaction at no additional cost.
11. The Contractor shall maintain all plant material and lawns until the project is fully accepted by the Landscape Architect, unless otherwise noted.
12. All workmanship and materials shall be guaranteed by the Contractor for a period of one calendar year after Final Acceptance.
13. Install all plant material in accordance with all local codes and ordinances. Coordinate with the Owner to obtain any required permits necessary to complete work.
14. Contractor shall test all tree pits for drainage. Any tree pit that holds water for more than 24 hours shall be installed using tree pit drainage.
15. Tree Protection Fencing is the responsibility of the Contractor. Minimum protected area shall include the full drip line of the canopy, NO construction activities, material storage, etc. may occur within that area. The Contractor shall ensure that no soil compaction or tree damage occurs in any Protected areas, at any time during the construction process.
16. Trees shall be matched in groups unless otherwise noted.

PLANTING LEGEND

- Lawn Seed Mix
- P4.0 Pavement, Aggregate
- P4.1 Decorative Landscape Stone, Refer to Specifications

ORDINANCE CHART
ZONING: Institutional
SURROUNDING ZONING
North: SF-2
East: SF-2
South: PUD
West: SF-2

OVERALL SITE REQUIREMENTS
Requirement: 2 Shade, 3 Ornamental or Evergreen, and 10 Shrubs/Acre
Required: 5 acres = 10 Shade, 15 Ornamental or Evergreen, and 50 Shrubs
Provided: 10 Shade, 15 Ornamental or Evergreen, and 81 Shrubs

STREET TREES
Street Trees not required

FOUNDATION PLANTINGS
Requirement: Provide plant material along walls and fences approx. every 40'

Required:

East: 174 l.f.
South: 269 l.f.
West: 101 l.f.
North: 239 l.f.


Provided:

East: Plantings are grouped to leave no more than 40' w/o plant coverage
South: Plantings are grouped to leave no more than 40' w/o plant coverage
West: Plantings are grouped to leave no more than 40' w/o plant coverage
North: Plantings are grouped to leave no more than 40' w/o plant coverage

BUFFERS
Northeastern Property Perimeter (100 LF)
Required: (Type B) 4 Shade, 4 Evergreen, 10 Shrubs, 4' Mound
Provided: 4 Shade, 4 Evergreen, 10 Shrubs, 4' Mound

INTERIOR PARKING LOT PLANTINGS
Required: 1 Shade, 4 Shrubs
Provided: 1 Shade, 4 Shrubs

PERIMETER PARKING
Perimeter Parking not required



CSO
8831 Keystone Crossing, Indianapolis, IN 46240
317-284-7800 | info@csocso.com

context
DESIGN
5825 Lawton Loop E. Dr., Indianapolis, IN 46216
317-485-6900 | www.context-design.com

PROJECT:
Westfield Washington Schools
ADDITION & RENOVATIONS TO
CAREY RIDGE ELEMENTARY
16231 CAREY ROAD, WESTFIELD, INDIANA 46074

SCOPE DRAWINGS:
These drawings indicate the general scope of the project in terms of architectural design concepts, the dimensions of structural, mechanical and electrical systems. The drawings do not necessarily indicate or describe all work required for the performance and completion of the project. The contractor shall verify all scope indicated or described, the trade contractors shall furnish all items required for the proper execution and completion of the work.

REVISIONS:
Addendum 01 10/18/2022
TAC Comment 03/15/2023
Response

ISSUE DATE 11/22/2022
DRAWN BY DDC
CHECKED BY LAM

DRAWING TITLE:
PLANTING
PLAN

CERTIFIED BY:
FEEDIE J. PRAZAU
REGISTERED
No. 2020-0052
STATE OF INDIANA
LANDSCAPE ARCHITECT
EXPIRES 12-31-2023


DRAWING NUMBER
L401

PROJECT NUMBER
2022020

GENERAL LANDSCAPE AND PLANTING NOTES

1. Refer to Project Manual for Planting Specifications and Topsoil requirements. Refer to Plant Schedule and Planting Details for additional information.
2. All materials are subject to the approval of the Landscape Architect and Owner at any time. Landscape Architect to inspect all plant locations and plant bed conditions prior to installation. On-site adjustments may be required.
3. Rootballs shall meet or exceed size standards as set forth in 'American Standards for Nursery Stock'. MAIN LEADERS OF ALL TREES SHALL REMAIN INTACT.
4. Remove from the site any plant material that turns brown or defoliates within five (5) days after planting. Replace immediately with approved, specified material.
5. Plant counts indicated on drawings are for Landscape Architect's use only. Contractor shall make own plant quantity takeoffs using drawings, specifications, and plant schedule requirements (i.e., spacing), unless otherwise directed by Landscape Architect. Contractor to verify bed measurements and install appropriate quantities as governed by plant spacing per schedule. Plant material quantities shown on plan are minimum quantities. Additional material may be needed to meet spacing requirements and field conditions.
6. Seed all areas disturbed by construction activities that are not otherwise noted to receive pavement, planting bed, or sod treatment.
7. The Contractor shall install and/or amend topsoil in all proposed bed areas to meet Specifications. Contractor shall coordinate quantity and placement of topsoil. Landscaper shall verify depth of topsoil prior to plant installation. (Refer to specifications for topsoil source and placement requirements)
8. All tree locations shall be marked with 2x2" stakes prior to planting for review and approval by the Landscape Architect. Any plant material installed in an incorrect location, by the judgment of the Landscape Architect, shall be reinstalled at the Contractor's expense.
9. All plant beds shall receive 3" minimum of shredded hardwood bark mulch (unless otherwise noted).
10. Verify all utility locations in the field prior to beginning work. Repair all damaged utilities to Owner's satisfaction at no additional cost.
11. The Contractor shall maintain all plant material and lawns until the project is fully accepted by the Landscape Architect, unless otherwise noted.
12. All workmanship and materials shall be guaranteed by the Contractor for a period of one calendar year after Final Acceptance.
13. Install all plant material in accordance with all local codes and ordinances. Coordinate with the Owner to obtain any required permits necessary to complete work.
14. Contractor shall test all tree pits for drainage. Any tree pit that holds water for more than 24 hours shall be installed using tree pit drainage.
15. Tree Protection Fencing is the responsibility of the Contractor. Minimum protected area shall include the full drip line of the canopy. NO construction activities, material storage, etc. may occur within that area. The Contractor shall ensure that no soil compaction or tree damage occurs in any Protected areas, at any time during the construction process. Trees shall be matched in groups unless otherwise noted.

PLANTING LEGEND



ORDINANCE CHART
ZONING: Institutional
SURROUNDING ZONING
North: SF-2
East: SF-2
South: PUD
West: SF-2

OVERALL SITE REQUIREMENTS
Requirement: 2 Shade, 3 Ornamental or Evergreen, and 10 Shrubs/Acre
Required: 5 acres = 10 Shade, 15 Ornamental or Evergreen, and 50 Shrubs
Provided: 10 Shade, 15 Ornamental or Evergreen, and 81 Shrubs

STREET TREES
Street Trees not required

FOUNDATION PLANTINGS
Requirement: Provide plant material along walls and fences approx. every 40'

Required:
East: 174 I.f.
South: 269 I.f.
West: 101 I.f.
North: 239 I.f.



Provided:
East: Plantings are grouped to leave no more than 40' w/o plant coverage
South: Plantings are grouped to leave no more than 40' w/o plant coverage
West: Plantings are grouped to leave no more than 40' w/o plant coverage
North: Plantings are grouped to leave no more than 40' w/o plant coverage

BUFFERS
Northeastern Property Perimeter (100 LF)
Required: (Type B) 4 Shade, 4 Evergreen, 10 Shrubs, 4' Mound
Provided: 4 Shade, 4 Evergreen, 10 Shrubs, 4' Mound

INTERIOR PARKING LOT PLANTINGS
Required: 1 Shade, 4 Shrubs
Provided: 1 Shade, 4 Shrubs


PERIMETER PARKING
Perimeter Parking not required

2



MATCHLINE - SEE SHEET L403

MATCHLINE - SEE SHEET L401



PROJECT:
Westfield Washington Schools
ADDITION & RENOVATIONS TO
CAREY RIDGE ELEMENTARY
16231 CAREY ROAD, WESTFIELD, INDIANA 46074

SCOPE DRAWINGS:
These drawings indicate the general scope of the project in terms of architectural design concept, the distribution of the building, the major mechanical and electrical systems, and the general site plan. The drawings do not necessarily indicate or describe all work required for full performance and completion of the project. The drawings are not to be used for construction or for any other purpose without the written consent of the architect.

REVISIONS:
Addendum 01 10/18/2022
TAC Comment 03/15/2023
Response

ISSUE DATE 11/22/2022
DRAWN BY DDC
CHECKED BY LAM


DRAWING TITLE:
PLANTING
PLAN



DRAWING NUMBER
L402

PROJECT NUMBER
2022020

No Work this Sheet



GENERAL LANDSCAPE AND PLANTING NOTES

1. Refer to Project Manual for Planting Specifications and Topsoil requirements. Refer to Plant Schedule and Planting Details for additional information.
2. All materials are subject to the approval of the Landscape Architect and Owner at any time. Landscape Architect to inspect all plant locations and plant bed conditions prior to installation. On-site adjustments may be required.
3. Rootballs shall meet or exceed size standards as set forth in 'American Standards for Nursery Stock'. MAIN LEADERS OF ALL TREES SHALL REMAIN INTACT.
4. Remove from the site any plant material that turns brown or defoliates within five (5) days after planting. Replace immediately with approved, specified material.
5. Plant counts indicated on drawings are for Landscape Architect's use only. Contractor shall make own plant quantity takeoffs using drawings, specifications, and plant schedule requirements (i.e., spacing), unless otherwise directed by Landscape Architect. Contractor to verify bed measurements and install appropriate quantities as governed by plant spacing per schedule. Plant material quantities shown on plan are minimum quantities. Additional material may be needed to meet spacing requirements and field conditions.
6. Seed all areas disturbed by construction activities that are not otherwise noted to receive pavement, planting bed, or sod treatment.
7. The Contractor shall install and/or amend topsoil in all proposed bed areas to meet Specifications. Contractor shall coordinate quantity and placement of topsoil. Landscaper shall verify depth of topsoil prior to plant installation. (Refer to specifications for topsoil source and placement requirements)
8. All tree locations shall be marked with 2x2" stakes prior to planting for review and approval by the Landscape Architect. Any plant material installed in an incorrect location, by the judgment of the Landscape Architect, shall be reinstalled at the Contractor's expense.
9. All plant beds shall receive 3" minimum of shredded hardwood bark mulch (unless otherwise noted).
10. Verify all utility locations in the field prior to beginning work. Repair all damaged utilities to Owner's satisfaction at no additional cost.
11. The Contractor shall maintain all plant material and lawns until the project is fully accepted by the Landscape Architect, unless otherwise noted.
12. All workmanship and materials shall be guaranteed by the Contractor for a period of one calendar year after Final Acceptance.
13. Install all plant material in accordance with all local codes and ordinances. Coordinate with the Owner to obtain any required permits necessary to complete work.
14. Contractor shall test all tree pits for drainage. Any tree pit that holds water for more than 24 hours shall be installed using tree pit drainage.
15. Tree Protection Fencing is the responsibility of the Contractor. Minimum protected area shall include the full drip line of the canopy. NO construction activities, material storage, etc. may occur within that area. The Contractor shall ensure that no soil compaction or tree damage occurs in any Protected areas, at any time during the construction process.
16. Trees shall be matched in groups unless otherwise noted.

ORDINANCE CHART
ZONING: Institutional
SURROUNDING ZONING
North: SF-2
East: SF-2
South: PUD
West: SF-2

OVERALL SITE REQUIREMENTS
Requirement: 2 Shade, 3 Ornamental or Evergreen, and 10 Shrubs/Acre
Required: 5 acres = 10 Shade, 15 Ornamental or Evergreen, and 50 Shrubs
Provided: 10 Shade, 15 Ornamental or Evergreen, and 81 Shrubs

STREET TREES
Street Trees not required

FOUNDATION PLANTINGS
Requirement: Provide plant material along walls and fences approx. every 40'

Required:
East: 174 l.f.
South: 269 l.f.
West: 101 l.f.
North: 239 l.f.


Provided:
East: Plantings are grouped to leave no more than 40' w/o plant coverage
South: Plantings are grouped to leave no more than 40' w/o plant coverage
West: Plantings are grouped to leave no more than 40' w/o plant coverage
North: Plantings are grouped to leave no more than 40' w/o plant coverage

BUFFERS
Northeastern Property Perimeter (100 LF)
Required: (Type B) 4 Shade, 4 Evergreen, 10 Shrubs, 4' Mound
Provided: 4 Shade, 4 Evergreen, 10 Shrubs, 4' Mound

INTERIOR PARKING LOT PLANTINGS
Required: 1 Shade, 4 Shrubs
Provided: 1 Shade, 4 Shrubs

PERIMETER PARKING
Perimeter Parking not required

2



PROJECT:
**Westfield Washington Schools
ADDITION & RENOVATIONS TO
CAREY RIDGE ELEMENTARY**
16231 CAREY ROAD, WESTFIELD, INDIANA 46074

SCOPE DRAWINGS:
These drawings indicate the general scope of the project in terms of architectural design concepts, the dimensions of structural, mechanical and electrical systems. The drawings do not necessarily indicate or describe all work required for the performance and completion of the project. On the basis of the general scope indicated or described, the trade contractors shall furnish all items required for the proper execution and completion of the work.

REVISIONS:
Addendum 01 10/18/2022
TAC Comment Response 03/15/2023

ISSUE DATE 11/22/2022
DRAWN BY DDC
CHECKED BY LAM


DRAWING TITLE:
**PLANTING
PLAN**

CERTIFIED BY:
FEODIE J. PRIZIAU
REGISTERED
No. 2020-0052
STATE OF INDIANA
LANDSCAPE ARCHITECT
EXPIRES 12-31-2023

DRAWING NUMBER
L403

PROJECT NUMBER
2022020

No Work this Sheet



GENERAL LANDSCAPE AND PLANTING NOTES

1. Refer to Project Manual for Planting Specifications and Topsoil requirements. Refer to Plant Schedule and Planting Details for additional information.
2. All materials are subject to the approval of the Landscape Architect and Owner at any time. Landscape Architect to inspect all plant locations and plant bed conditions prior to installation. On-site adjustments may be required.
3. Rootballs shall meet or exceed size standards as set forth in "American Standards for Nursery Stock". MAIN LEADERS OF ALL TREES SHALL REMAIN INTACT.
4. Remove from the site any plant material that turns brown or defoliates within five (5) days after planting. Replace immediately with approved, specified material.
5. Plant counts indicated on drawings are for Landscape Architect's use only. Contractor shall make own plant quantity takeoffs using drawings, specifications, and plant schedule requirements (i.e., spacing), unless otherwise directed by Landscape Architect. Contractor to verify bed measurements and install appropriate quantities as governed by plant spacing per schedule. Plant material quantities shown on plan are minimum quantities. Additional material may be needed to meet spacing requirements and field conditions.
6. Seed all areas disturbed by construction activities that are not otherwise noted to receive pavement, planting bed, or sod treatment.
7. The Contractor shall install and/or amend topsoil in all proposed bed areas to meet Specifications. Contractor shall coordinate quantity and placement of topsoil. Landscaper shall verify depth of topsoil prior to plant installation. (Refer to specifications for topsoil source and placement requirements)
8. All tree locations shall be marked with 2x2" stakes prior to planting for review and approval by the Landscape Architect. Any plant material installed in an incorrect location, by the judgment of the Landscape Architect, shall be reinstalled at the Contractor's expense.
9. All plant beds shall receive 3" minimum of shredded hardwood bark mulch (unless otherwise noted).
10. Verify all utility locations in the field prior to beginning work. Repair all damaged utilities to Owner's satisfaction at no additional cost.
11. The Contractor shall maintain all plant material and lawns until the project is fully accepted by the Landscape Architect, unless otherwise noted.
12. All workmanship and materials shall be guaranteed by the Contractor for a period of one calendar year after Final Acceptance.
13. Install all plant material in accordance with all local codes and ordinances. Coordinate with the Owner to obtain any required permits necessary to complete work.
14. Contractor shall test all tree pits for drainage. Any tree pit that holds water for more than 24 hours shall be installed using tree pit drainage.
15. Tree Protection Fencing is the responsibility of the Contractor. Minimum protected area shall include the full drip line of the canopy. NO construction activities, material storage, etc. may occur within that area. The Contractor shall ensure that no soil compaction or tree damage occurs in any Protected areas, at any time during the construction process.
16. Trees shall be matched in groups unless otherwise noted.

ORDINANCE CHART
ZONING: Institutional
SURROUNDING ZONING
North: SF-2
East: SF-2
South: PUD
West: SF-2

OVERALL SITE REQUIREMENTS
Requirement: 2 Shade, 3 Ornamental or Evergreen, and 10 Shrubs/Acre
Required: 5 acres = 10 Shade, 15 Ornamental or Evergreen, and 50 Shrubs
Provided: 10 Shade, 15 Ornamental or Evergreen, and 81 Shrubs

STREET TREES
Street Trees not required

FOUNDATION PLANTINGS
Requirement: Provide plant material along walls and fences approx. every 40'

Required:
East: 174 l.f.
South: 269 l.f.
West: 101 l.f.
North: 239 l.f.


Provided:
East: Plantings are grouped to leave no more than 40' w/o plant coverage
South: Plantings are grouped to leave no more than 40' w/o plant coverage
West: Plantings are grouped to leave no more than 40' w/o plant coverage
North: Plantings are grouped to leave no more than 40' w/o plant coverage

BUFFERS
Northeastern Property Perimeter (100 LF)
Required: (Type B) 4 Shade, 4 Evergreen, 10 Shrubs, 4' Mound
Provided: 4 Shade, 4 Evergreen, 10 Shrubs, 4' Mound

INTERIOR PARKING LOT PLANTINGS
Required: 1 Shade, 4 Shrubs
Provided: 1 Shade, 4 Shrubs

PERIMETER PARKING
Perimeter Parking not required

2



CSO
8831 Keystone Crossing, Indianapolis, IN 46240
317-485-7800 | ccontnet

context
DESIGN
5825 Lawton Loop E.D., Indianapolis, IN 46216
317-485-4900 | www.context-design.com

PROJECT:
Westfield Washington Schools
ADDITION & RENOVATIONS TO
CAREY RIDGE ELEMENTARY
16231 CAREY ROAD, WESTFIELD, INDIANA 46074

SCOPE DRAWINGS:
These drawings indicate the general scope of the project in terms of architectural design concept, the dimensions of the building, the major structural and electrical systems. The drawings do not necessarily indicate or describe all work required for full performance and completion of the project. The contractor shall verify all items required for the proper execution and completion of the work.

REVISIONS:
Addendum 01 10/18/2022
TAC Comment 03/15/2023
Response

ISSUE DATE 11/22/2022
DRAWN BY DDC
CHECKED BY LAM

DRAWING TITLE:
PLANTING
PLAN


CERTIFIED BY:
FEEDIE REGISTERED
No. 2020-0052
STATE OF INDIANA
LANDSCAPE ARCHITECT
EXPIRES 12-31-2023

DRAWING NUMBER
L404

PROJECT NUMBER
2022020

PLANT SCHEDULE

DECIDUOUS TREES	QTY	BOTANICAL NAME	COMMON NAME	CONT	CAL	SIZE	REMARKS
Gle-s	3	Gleditsia triacanthos inermis 'Shademaster'	Shademaster Thornless Honeylocust	B & B	2"Cal	min. 8' ht.	full, strong central leader, matched
Lir-t	4	Liriodendron tulipifera	Tulip Tree	B & B	2"Cal		full, strong central leader, matched
Que-r	3	Quercus rubra	Red Oak	B & B	2"Cal		spring dug, full, strong central leader, matched
EVERGREEN TREES	QTY	BOTANICAL NAME	COMMON NAME	CONT	CAL	SIZE	REMARKS
Pic-p	4	Picea pungens glauca 'Fat Albert'	Fat Albert Colorado Blue Spruce	B & B		min. 6' ht.	full, strong central leader, matched, symmetrical
FLOWERING TREES	QTY	BOTANICAL NAME	COMMON NAME	CONT	CAL	SIZE	REMARKS
Ame-x	5	Amelanchier x grandiflora 'Autumn Brilliance'	Autumn Brilliance Serviceberry	B & B	2" Cal	min. 8' ht.	multi-trunk; matched
Cer-c	6	Cercis canadensis	Eastern Redbud	B & B	2"Cal	8' ht.	multi-trunk, matched
SHRUBS	QTY	BOTANICAL NAME	COMMON NAME	SIZE	HEIGHT	FIELD3	REMARKS
Cor-c	6	Cornus sericea 'Kelsey'	Kelseyi Red Twig Dogwood	container	24"		space @ 2'-6" o.c.
Cor-a	18	Cornus stolonifera 'Farrow'	Arctic Fire Dogwood	container	24"		space @ 3'-0" o.c.
Hyd-a	11	Hydrangea arborescens 'Abetwo'	Incrediball Hydrangea	container	24"		space @ 5'-0" o.c.
Ite-s	16	Itea virginica 'Sprich'	Little Henry Virginia Sweetspire	container	24"		space @ 3'-0" o.c.
Myr-p	15	Myrica pensylvanica	Northern Bayberry	container	24"		space @ 8'-0" o.c., allow to mass
Vib-d	15	Viburnum dentatum 'Christom'	Blue Muffin Viburnum	container	24"		space @ 4'-0" o.c.
GRASSES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	HEIGHT	FIELD3	REMARKS
Pan-v	20	Panicum virgatum 'Cloud Nine'	Cloud Nine Switch Grass	#1 pot			space @ 3'-0" o.c.



NOTES:

1. Refer to tree protection specifications.
2. Contractor may submit alternate methods of tree protection to Landscape Architect for consideration.

8 TREE PROTECTION

Not To Scale

TRENCHING/EXCAVATION

ZONE A (CRITICAL ROOT ZONE)

1. NO DISTURBANCE ALLOWED without site-specific inspection and approval of methods to minimize root damage.
2. Severance of roots larger than 2" diameter requires Landscape Architect's approval.
3. Tunneling or boring required to install utilities 3'-0" below grade or deeper.

ZONE B (DRIPLINE)

1. Operation of heavy equipment and/or stockpiling of materials subject to Landscape Architect's approval. Surface Protection" measures required.
2. Trenching allowed as follows:
 - Excavation by hand or with hand-driver trencher may be required.
 - Limit trench width. Do not disturb Zone A, maintain 2/3 or more of Zone B in undisturbed condition.
3. Tunneling or boring may be required for trenches deeper than 3'-0".

ZONE C (FEEDER ROOT ZONE)

1. Operation of heavy equipment and/or stockpiling of materials subject to Landscape Architect's approval. Surface Protection" measures required.
2. Trenching with heavy equipment allowed as follows:
 - Minimize trench width.
 - Maintain 2/3 or more of Zone C in undisturbed condition.

FENCING/ROOT PROTECTION


4' high vinyl protection fence at the greater of Zone B (Dripline) or to a radius (in feet) of 1.5x the caliper (in inches) of the tree, minimum, and at Zone C (Feeder Root Zone) if possible. Refer to Detail this Sheet.

Upon Landscape Architect's approval, a plywood box (8' minimum height) may be used where fencing cannot be achieved.

Landscape Architect's approval required for use/access within Zone B. Permission for use/access requires Surface Protection Measures for all unfenced, unpaved surfaces within Zone B.


*SURFACE PROTECTION MEASURES

1. Mulch Layer, 6"-8" Depth
2. 3/4" Plywood
3. Steel Plates




7 DECORATIVE LANDSCAPE STONE

Not to Scale




6 METAL EDGE

Not to Scale




5 SHRUB PLANTING

Not to Scale




4 SPADE EDGE

Not to Scale




3 GROUNDCOVER PLANTING

Not to Scale



2 MULTI-STEM TREE PLANTING

Not to Scale



1 TREE PLANTING

Not to Scale

